

|                  |                               |     |     |      |
|------------------|-------------------------------|-----|-----|------|
| Document Number  | FTT                           | NAT | PRC | 0053 |
| Next Review Date | 13 <sup>th</sup> January 2022 |     |     |      |
| Document Owner   | National Procurement Manager  |     |     |      |

# FIRE SUPPRESSION – MOBILE PLANT - SCOPE OF WORK

## 01 Describe the work to be performed

- Design, install, modify and maintain fire suppression systems and equipment on Caterpillar and other OEM mobile plant
- This includes, but is not limited to automatic detection systems, automatic and manual activated suppression systems and fire extinguishers
- Comply with ISO 9001:2008 ISO standards
- Comply with AS5062:2016 - Fire Protection for mobile and transport equipment
- Provide the following for each installation;
- Operator instructions and training manual, Operations and Maintenance manuals, Electrical and Hydraulic Schematics, Commissioning Report/checklist
- Provide a copy of the fire risk assessment for each system installed on a WesTrac or customer machine
- All other requirements per the Principal Scope of Works

## 02 Extra requirements to the Pre-Qualification

- Have a policy/procedure for the damage of machinery
- Ensure all testing devices being used are calibrated, and records of all to be provided
- All designs to be vetted through WesTrac Engineering where practicable
- All other requirements per the Principal Scope of Works

## 03 Other Scopes of Work required or relevant to this task

- Use of hand and power tools
- Use of hazardous substances
- Mobile plant modification
- Working at heights
- Hot works

## 04 Inductions required & DMS policies and procedures required for this Scope of Work

- As per the Principal Scope of Works

## 05 Describe who supplies the materials

- As per the Principal Scope of Works

## 06 Describe how the work will be measured

- Any alterations must be subject to a quality control check/test against the pre-agreed scope of work. This must be documented fully, and witnessed and approved by a representative of the contractor and a responsible person from WesTrac
- All other requirements per the Principal Scope of Works

## 07 Describe at what point will the work be accepted

- The modification will be accepted when the quality control check has been approved, and the necessary documentation has been received, checked and approved. The works will not be marked as complete until the documentation is received
- All other requirements per the Principal Scope of Works